

R-6020/ce  
9-7-18  
Department Of Electricity

1<sup>st</sup> Call

(Supply Service Section)  
Aligarh Muslim University -Aligarh

D. No. 514 /SSS

Dated. 09.07.18

**Notice Inviting Quotation**

On behalf of the Department of Electricity (SSS), A.M.U. Aligarh, quotations are invited from the registered venders /suppliers / Manufacturers under limited tender enquiry for the following works, the details mentioned below:-

S.No.	Name of Items	Place of Work
1.	Providing and laying Cable for Generator supply from 62.5 KVA Generator Main Panel to New OPD Block at A.K. Tibbiya College and Hospital AMU, Aligarh as per BOQ attached	A.K. Tibbiya College

- 1) Complete Description and Term & Conditions of Quotation Document may be obtained from AMU website <http://www.amu.ac.in/tender.jsp?did=02> directly or from the office of the Assistant Electrical Engineer (SSS), AMU, Aligarh on any working day.
- 2) Incomplete Tender / Quotation or if not mentioned all Item rates will be rejected.
- 3) The make and model No of the items to be supplied should be mentioned separately with warranty period and payment Terms & Conditions.
- 4) Quotation duly completed in all respect should reach the **Assistant Electrical Engineer, Department of Electricity (Supply Service Section), AMU, Aligarh** by registered post or in person on **17.07.2018 (Tuesday) up to 12: 00 Hrs.**
- 5) Date and Time of opening of Quotation: **17.07.2018 (Tuesday) at 15: 00 Hrs.**
- 6) If the date of receipt or opening of quotation is declared to be a public holiday, the quotation will be received and opened on the next working day at the same time.
- 7) University reserves the right to change the quotation opening date and time totally at its discretion.
- 8) University reserves the right to reject any or all the quotations without assigning any reason thereof and to call for any other details or information from any of the quotation.

Copy to:-


1. Director, Computer Centre with the request to arrange to upload the NIQ at Concerned Web-site.
2. Principal, A.K. Tibbiya College & Hospital for kind information.
3. Member-In-Charge for kind information.
4. Notice Board of Electricity Department/Office Record.

*Shamim*  
09/07/2018  
Er. Mohd Shamim Ansari  
Assistant Electrical Engineer (SSS)  
Department of Electricity  
A.M.U., Aligarh

*Shamim*  
09/07/2018  
Er. Mohd Shamim Ansari  
Assistant Electrical Engineer (SSS)  
Department of Electricity (SSS)  
A.M.U., Aligarh

**BILL OF QUANTITY FOR PROVIDING / LAYING CABLE FOR GENERATOR SUPPLY  
FROM 62.5 KVA GENERATOR MAIN PANEL TO THE NEW OPD BLOCK AT A.K. TIBBIYA  
COLLEGE AND HOSPITAL AMU, ALIGARH.**

S. No.	DESCRIPTION	QTY.	UNIT	RATE	AMOUNT
1	Supplying of 4 core 16 Sq mm PVC Insulated and PVC Sheathed Aluminium Conductor Heavy duty armoured Cable 1.1 KV grade (Havells / KEI make)	150	Mtrs.		
2	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of the following size direct in ground including excavation, sand cushioning, protective covering and refilling the trench etc as required.  (a) upto 35 sq mm	25	Mtrs.		
3	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of the following size in the existing masonry open duct as required.  (a) upto 35 sq mm	75	Mtrs.		
4	Laying and fixing of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of the following size on the wall surface as required.  (a) upto 35 sq mm ( clamped with 1mm thick saddle )	50	Mtrs.		
5	Providing , Fixing , testing and commisioning of four pole, 63 Amp, 415 Volts on load Changeover switch on the cubical panel board including drilling holes in cubical panel making connection etc as required make seimens / legrand / & L&T	1	Nos.		
6	Supplying and fixing 100Amp, MCCB Enclosure with blanking plate on the suitable size of Angle Iron frame (50mm X 50mm X 6mm) or in recess including drilling holes in frame , etc as required. Cat No. IHEAFP (seimens / L&T / Legrand / make ).	2	Nos		
7	Providing , fixing ,testing and commisioning of four pole 100Amp , 25KA , 240Volts MCCB on the above enclosure including drilling holes in cubical panel , making connections etc as required ( Seimens , L&T , Legrand, make ).	1	Nos.		
8	Providing , fixing ,testing and commisioning of four pole 63Amp , 25KA , 240Volts MCCB on the above enclosure including drilling holes in cubical panel , making connections etc as required ( Seimens , L&T , Legrand, make ).	1	Nos.		
9	Supplying and fixing (crimping) Aluminium lugs for PVC Insulated and PVC Sheathed / XLPE Power Aluminium Conductor cable of 1.1 KV grade of following size as required.  (a) 2 core 16 Sq mm cable (Make Action /Dowells).	8	Set.		
	<b>TOTAL</b>				

  
 Assistant Electrical Engineer  
 Department of Electricity (SSS)  
 A.M.U., Aligarh

09/09/2018

MBib

