

Tender Notice (Open Tendering)

Manufacturers and Vendors are invited to submit their quotations for the **Air Conditioning of Kennedy Auditorium**, Aligarh Muslim University, Aligarh (U.P). The quotations along with company profile (in a sealed envelope) should reach to the following address on or before 17th June 2015.

Address:

Coordinator

Cultural Education Centre

Kennedy House Complex

Aligarh Muslim University, Aligarh (U.P) 202001.


**COORDINATOR
CEC, AMU
ALIGARH**

BILL OF QUANTITIES FOR KENNEDY HALL,AMU,ALIGARH

Sr No.	DESCRIPTION	UNIT	QTY.	RATE (Rs.)	AMOUNT (Rs.)
1	PART "A" AC EQUIPMENT				
1.1	FLOOR STANDING PACKAGE AC Units WITH ECO FRIENDLY REFRIGERENT-410A				
	Supply, installation, testing and commissioning of Floor standing Package air conditioning system (air-cooled type) complete with compressor, air-cooled condenser, DX-coil, filters, blowers section with motor and drive, interconnected refrigerant piping, first charge of refrigerent gas (R-410A) and oil, HP/ LP cut out, thermostatic expansion valve distributor, starter, support for indoor unit and other necessary controls to form a factory tested compact unit. All items should be encased in enamel painted anti corrosive sheet metal				
a)	Capacity : 15 TR (18HP)	Nos.	2		
b)	Capacity : 8.5 TR (10HP)	Nos.	17		
1.2	Hi-Wall Split AC Units With Eco Friendly Refrigerent-410A/R-32				
	Supply, installation, testing and commissioning of Air Cooled type Wall Mounted Split Air-Conditioning unit,each comprising of an outdoor unit and a single slim indoor unit. Outdoor condensing unit shall comprise of rotary compressor with first charge of refrigeren gas (R-410 A/R-32) & air cooled condenser with fan. Evaporating unit shall consist of a blower section with dynamically balanced centrifugal blower driven by TEFC squirrel cage induction motor, multirows deep copper cooling coil with aluminium fins, thermostatic expansion valve etc. The evaporating unit shall be equipped with synthetic fibre filters, insulated drain pan, safety controls, thermostat all complete in a unit along with the suitable stablizer.				
	The units shall be suitable for 230V±6%,50 Hz supply.(3 star)				
a)	1.5 TR	Nos.	8		
1.3	Frame Work				
	Supply, fabrication and installation of MS base frame for outdoor units complete with epoxy painting, vibration isolation pads, supports hangers, railing, brackets etc.				
	Ductable AC Units				

